

## Parks, Recreation & Culture

### REQUEST FOR QUOTATIONS

Cupola Repairs, Burntcoat Head Park Lighthouse  
RFQ50152 - Addendum 1

Release date: March 2, 2017

Quotations will be received up to  
3:00:00 pm local time on Tuesday, March 14, 2017

Contact: Michael Hatfield  
Procurement Officer  
Municipality of East Hants  
Telephone: (902) 883-7098, Ext 232  
Email: [mhatfield@easthants.ca](mailto:mhatfield@easthants.ca)



**EAST HANTS**  
We live it!

# Contents

1. Additions/Clarifications ..... 3



## 1. Additions/Clarifications

### 1.1.1. Add the following to Section 2, subsection 2.2.5.2.3.:

“Remove the wooden stop around the exterior of the panes of glass in each panel and install the membrane (blueskin) so that it laps up onto the glass forming a continuous barrier over the seams where the glass meets the wooden structure, but behind the wooden stop. Reinstall the stop. The membrane must not be visible above the edge of the interior stop, from the inside, once the stop has been reinstalled.”

The intent is prevent water from entering the window frame where the glass meets wooden structure.

### 1.1.2. Add following to Section 3:

#### **“WORKERS’ COMPENSATION**

The Contractor must be registered and in good standing with the Workers’ Compensation Board of Nova Scotia (WCBNS) regardless of their jurisdiction of incorporation, location of premises, or typical status with WCBNS prior to commencing the work and proof must be provided to East Hants in the form of a valid Clearance Letter confirming they are in good standing with WCBNS.

No payments will be made by East Hants to the Contractor unless their invoice is accompanied by a valid Clearance Letter confirming they are in good standing with WCBNS.”

Note that a Contractor who is not currently registered with WCBNS may still bid provided they declare their intention to register in Appendix B. In such case, the Contractor would need to register with WCBNS and be in good standing prior to the start of the work.

### 1.1.3. Access to the site:

If a Contractor needs to bring material and equipment to the Lighthouse in a truck, they must follow the fence line to the right of the Lighthouse when facing the ocean. Other routes are limited by pedestrian bridges which are not designed or suitable for truck or equipment travel.

